

National Institute of Plant Genome Research

Aruna Asaf Ali Marg, Near ICSSR, JNU Campus, New Delhi – 110067

Phone: 26735161, 26735138 Fax: 26741658

F. No. NIPGR/7/66(A)/Mtce./Vol.II /

Dated: 30.01.2014

NOTICE INVITING QUOTATIONS

Sealed item rate quotations are invited on behalf of the Director, NIPGR, New Delhi, from approved & eligible contractors in respect of the following work, so as to reach his office on or before - 14.02.2014 up to 3.00 P.M. The quotation shall be opened on the same day at 3.30 P.M. in presence of the intending quotationers.

SCHEDULE OF QUANTITY

Name of Work: Repairing of Vitrified flooring in Students Hostel Building at NIPGR, New Delhi.

Sl. No.	Description	Qty.	UNIT	Rate (in Rs.)	Amount (in Rs.)
	As per enclosed Schedule of Quantity and Terms & Conditions				

Encl.: 1. Schedule of quantity.
2. Terms & conditions.

Consultant Engineer
NIPGR, New Delhi

M/s _____

Seal & Signature of Contractor

Schedule of Quantity					
Name of Work: Repairing of Vitrified flooring in Student Hostel Building at NIPGR New Delhi					
S.N.	Description	Unit	Qty	Rate	Amount
1	Dismantling of tile work in floors laid in cement mortar including stacking material within 50metres lead.				
	for thickness of tiles 10mm to 25 mm	Sqm	125		
2	Demolishing cement concrete manually/by mechanically means including disposal of material within 50 metres lead as per direction of Engineer-in-charge,	Cum	4		
3	Providing and laying vitrified tiles(old & new) in different sizes(thickness to be specified)with water absorption less than 0.08% and confirming to IS:15622, of approved brand & manufacturer, in all clours and shades, laid on 20mm thick cement mortar 1:4(1cement:4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete per direction of Engineer-in-charge(cost of Tiles shall be paid separately. tiles stacked after dismantle will also be used)				
	Sizeof tiles-600X600mm	Sqm	75		
4	Fixing vitrified floor tiles with cement based high polymer modified quick -set tiles adhesive(water based) confirming to IS:15477, in average 3 mm thickness as per direction of Engineer-in-charge,	sqm	50		
5	Deduct for not using 20mm thick cement mortar 1:4(1 cement: 4 coarse Sand) bedding in laying of floor tiles as per direction of Engineer-in-charge,	Sqm	50		
6	Supply of vitrified tiles in different sizes(thickness to be specified)with water absorption less than 0.08% and confirming to IS:15622, of approved brand & manufacturer, in all clours and shade etc. complete as per direction of Engineere-in-charge.	Sqm	100		
		Total Amount			
		(In words Rs.-----)			
		Consultant Engineer			
		NIPGR New Delhi			
Seal & Signature of Contractor					

TERMS & CONDITIONS

Name of Work: Repairing of Vitrified flooring in Student Hostel Building at NIPGR New Delhi

1. The contractor should visit the site and make himself acquainted with the location .The Department shall entertain no extra claim later on.
2. The site of work is at NIPGR Campus, Aruna asaf Ali Marg New Delhi-110067.
3. The contractor shall make his own arrangement for the safe custody of material at site.
4. The contractor shall arrange all T&P; scaffolding arrangement to access the work locations and nothing will be extra paid.
5. Contractor should be responsible for all safety precaution at work.
6. The contractor must get the **prior approval of materials** from the Engineer- In -Charge.
7. The rates shall be inclusive of Transportation, loading, unloading and handling charges and nothing extra will be paid.
8. The rates shall be inclusive of all taxes including VAT & Service tax and nothing extra will be paid.
The rates shall be finished items of work
9. The contractor shall follow all labour laws as prevailing in Delhi.
10. All works shall be completed to the entire satisfaction of the Engineer-in-charge.
11. The Director reserves the right to reject / accept any or all quotation without assigning any reason.
12. In case of any dispute the decision of the Engineer-in-charge shall be final & binding on the contractor.
13. Any work not carried out as per instruction of the Engineer-in-charge shall be dismantled and reconstructed by the contractor without any extra cost.
14. The work shall be completed in all respects within **Ten days** from the date of issue of work order.
Being time bound, contract, and the contractor shall be liable to pay compensation @1. % per per day subject to maximum 10% of W.O. amount if the work is not completed within stipulated time of Completion.
15. The agency must be expertise, experienced in the construction of civil works.
16. The value of work of similar nature shall not less than 1.50 lakhs per year in last three years to be done. Completion certificate must submitted with quotation.
17. The Contractor shall be responsible for any damages and site clearance and nothing extra will be paid. In case the site clearance and damages are not attended, a recovery amounting to ₹5000/- (Rs. Five thousand only) shall be made.
18. The quotation must be accompanied with EMD of ₹ 3480 (₹Three thousand & Four Hundred Eighty only). The earnest money (EMD) shall be in the form of DD of scheduled bank drawn in favour of **"Director NIPGR" New Delhi. Without EMD quotation shall not be considered.**
19. Security deposit @ 10% shall be deducted from the bill and shall be refunded after the completion of defect liability period of **Six Months**. The EMD will however be adjusted towards security deposit.
20. All papers attached with this Quotation should be signed & returned in original.

Consultant Engineer

NIPGR, New Delhi

PAN-----

TIN-----

Seal & Signature of Contractor